


COMBINATION CURB AND GUTTER



MEDIAN

GUTTER

SIDE ELEVATION CURB AND

NOTES:

- CONCRETE SHALL BE 4,000 P.S.I.
 CONTRACTION JOINTS SHALL BE SPACED AT 10' INTERVALS.
 (A 15' SPACING WILL BE ALLOWED WHEN A MACHINE IS USED.)
 EXPANSION JOINTS SHALL BE PLACED EVERY 40'

DATE REVISIONS DESCRIPTION

ENGINEERING 0F ASHEVILLE, DEPARTMENT N.C.

CITY

ASHEVILLE

STANDARD CONCRETE CURB AND GUTTER

> STD. Z 0.

3.11